6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Item of work	Per	Quantity
Bund—		
Earthwork	C. yd.	13,345
Turfing	S. yd.	8,139
New stone work, with jelly	C. yd.	1,632
Old stone work	,,	920
Gravel booking to revetment	,,	678
Grade stones including painting	Each	27
Index stones do	,,	27
Gauge stone	,,	1
Number and year stone	,,	2
Removing prickly-pears and jungle	Lump sum	
Sluice—		
Repairing the existing sluice	Do	
Constructing a new sluice near C. S. No. 10	Do	
Waste weir, right, 81 feet long—		
Earthwork, excavation	C. yd.	320
Benching rock	S. ft.	524
Burnt stone in chunam	C. ft.	2,145
Burnt stone slabs	S. ft.	467
Pointing with chunam	Sqr.	13·12

Notification dated 26th February 1906.

The attention of the public is invited to the notification in the *Mysore Gazette*, No. 9, dated 1st March 1906, calling for tenders for restoring the Tayalur Amanikere Tank, Registered No. 88 of Mulbagal Taluk.

K. KRISHNA IYENGAR, *Executive Engineer.*

IN THE COURT OF THE ASSISTANT COMMISSIONER AND 1ST CLASS MAGISTRATE, HONNALI DIVISION, SHIMOGA.

Notice dated 3rd March 1906.

Notice is hereby given that a sum of Rs. 78-11-6, being the sale proceeds of certain cloths belonging to one Marvadi Himmat Mal of Ayanur, Shimoga Taluk, complainant in Criminal Case No. 74 of 1903-04 on the file of this Court, who is reported to be dead, remains unclaimed in this Court.

The legal representatives of the deceased should apply to this Court for the said amount within six months from this date, failing which the amount will be credited to Government.

K. MATHAN, *1st Class Magistrate.*

CHITALDRUG DIVISION.

Dated 10th March 1906.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Chitaldrug Division, up to forenoon of 27th March 1906, for constructing a combined Sub-Taluk Cutcherry and Sub-Registrar's office at Harihar. An approximate estimate of quantities is given below. The quantities are not guaranteed. The work should be completed by the end of June 1907.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chitaldrug between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a combined Sub-Taluk Cutcherry and Sub-Registrar's office at Harihar, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate for constructing Sub-Taluk Cutcherry at Harihar.

Items of work	Per	Main building	Lock-ups	Total
		Quantity	Quantity	Quantity
Earthwork, excavation	C. yd.	238	131	370
Gravel filling	Do	135	..	135
Concrete foundation	C. ft.	1,598	701	2,299
Burnt stone in chunam	Do	5,727	2,447	8,174
Burnt brick in chunam	Do	7,551	4,576	12,127
Do archwork	Do	504	23	527
Burnt stone slabs dressed	S. ft.	479	279	758
Chunam plastering	Sqr.	126·24	63·16	189·40
Do pointing	Do	5·06	2·45	7·51
White and color washing	Do	131·30	65·21	196·51
Teakwood work with wood-oiling	C. ft.	500·89	86·30	587·19
Roofing with 1st class Mangalore flat tiles with teak reepers, etc., complete.	Sqr.	8·19	..	8·19
Ridge tiles set in mortar	R. ft.	32	..	32
Ventilating tiles	Each	6	..	6
Pucka terrace 9" thick	Sqr.	24·87		24·87
Teakwood door half panelled and half venetianed with hinges, bolts, etc.	S. ft.	289	23	312
Teakwood windows, double shutters battened outside, glass double shutters inside and iron bars with fan lights at top.	Do	185	..	185
Teakwood ventilators glazed, etc.	Do	85	..	85
Do windows battened with iron bars ...	Do	...	35	35
Do doors half battened and half barred ..	Do	..	137	137
Do ventilators with iron bars and perforated iron webbing.	Do	..	68	68
Flooring with Mangalore tiles over 3" concrete and cement pointing.	S	19·13	..	19·13
Flooring with Cuddapah slabs over 3" concrete and cement pointing.	Do	6·41	5·17	11·58
Ceiling with teak planks ½" thick	Do	..	5·70	5·70
Zinc gutters for roof drainage	L. S.	L. S.	.	L. S.
Eave board (teak)	R. ft.	...	144	144
Prisoner's dock; witness box, Judge's seat and wooden screen to Amildar's and Sub-Registrar's rooms.	L. S.	L. S.	..	L. S.
Clearing compound, levelling site and making road ...	Do	Do	.	Do
Cornice work	R. ft.	349	..	349
Finials	Each	2	..	2
Chacolate painting	Sqr.	13·00	..	13·00
Brick in chunam capitals on top of pilasters ..	Each	7	..	7
Compensation for land	L S.	L. S.	..	L. S.
Fencing the compound	Do	Do		Do
Excavating trench around compound	Do	..	L. S.	Do
Clearing site	Do	...	Do	Do
Date stone	Each	...	1	1

K. PRAHLADA RAO,
Executive Engineer.